

Job: SnowCrest  
From: K2 Enterprises  
Date: 11-29-16/3-27-17  
Re: Hot Tub Project

Work to be done:

- Remove old hot tub
- Remove decking
- Remove existing railings and gate
- Remove upper fencing and save for re-installation (excavation access)
- Conduct framing alterations to existing deck frame
- Excavate area for new hot tub and retaining wall
- Haul off dirt
- Form concrete retaining wall and place rebar according to engineering specs
- Install bench support brackets into retaining wall form
- Pour concrete retaining walls for new hot tub
- Install drain system for wall
- Back-fill walls
- Construct additional foundation and framing for new decking
- Install new composite decking
- Construct composite bench
- Construct new rail system (cable)
- Construct and install new gate
- Finish grade and seed grass area above hot tub

Notes:

- Job includes all materials and labor
- Job includes all removal of debris
- Job includes all clean-up
- Price does not include permit fees and addition engineering costs

Total Estimated Time Required: 3-4 weeks (weather dependent)

Total Cost: \$48,230.00